

Screw compaction unit for installation in free fall of material

SFM4



The SFM4 bypass screw compaction unit has to be placed in a free fall situation of material, e.g. in a drop shaft. A partial flow of this material is trapped in the first section of the compaction unit. The screw compactor compresses the material and conveys it into the second part of the unit, right across the installed ACO moisture sensor for the determination of the residual moisture. Then the material falls down through a drop pipe back into the process.

Overview of Features

- Ideal material conditions for the on-line moisture measurement
- Flexible mounting of the bypass screw conveyor
- Subsequently applicable
- Great experience in the field of saw dust
- Maintenance flap for taking samples



Based on this constant and equal conditions (density, dumping height, etc...) precise measuring results are available.

Screw compaction unit for installation in free fall of material

SFM4



Technical Details

NA 1 2 1	
Material	Stainless steel
Dimensions, over all	900 x 490 x 450 (L x B x H in mm)
Troughput	ca. 1,2 m³/h
Connected load (motor)	400 V AC / 50 Hz / 1,35 A / 0,55 kW
Scope of delivery	Screw compaction unit complete with gear motorClamp flange for ACO moisture measuring sensor
Optional: Certification, ATEX	Motor: II 3D Ex tc IIIB T120°C Dc Gear: II 2GD c, k T4/T120C
Optional	Length, height, dimensions of flanges on customer requirements





ACO Automation Components | Johannes Mergl e.K. Feuchtemessung | Moisture measurement Industriestrasse 2 | D-79793 Wutöschingen Tel. +49 (0) 77 46 91316 | Fax +49 (0) 77 46 91317 info@acoweb.de | www.acoweb.de

